


EXISTING FRAME INFORMATION



- INSTRUCTIONS FOR MANUFACTURED REPLACEMENT DOOR PANEL TO FIT AN EXISTING FRAME
- ALL DIMENSIONS & QUESTIONS MUST BE FILLED IN COMPLETELY & ACCURATELY
 - MEASURE THE EXISTING FRAME, NOT THE EXISTING DOOR PANEL
 - PROVIDE THE DOOR FRAME OPENING DIMENSIONS, NOT THE DOOR PANEL DIMENSIONS
 - ANSWER ALL ADVISES UNDER THE SPECIAL NOTES SECTION

3 HINGES



VERTICAL DIMENSION FROM FINISHED FLOOR NOT FRAME BOTTOM.
(NOTE: DOOR UNDERCUT WILL BE DETERMINED FROM LARGEST VERTICAL DIMENSION)

- * QUESTIONS TO BE ANSWERED: (BE PRECISE ON MEASUREMENTS) *
- 1.* HINGE BACKSET & DEPTH OF RABBIT? (SEE DETAIL)
- 2.* ACTUAL HINGE THICKNESS?
- 3.* HINGE LOCATIONS? FROM TOP OF FRAME OPENING TO TOP OF EACH HINGE
- 4.* ACTUAL STRIKE THICKNESS? (IF APPLICABLE)
- 5.* STRIKE LOCATION? FROM TOP OF FRAME OPENING TO TOP OF STRIKE & TOP OF FRAME OPENING TO CENTERLINE OF STRIKE (IF APPLICABLE)
- 6.* IS THE FRAME SQUARE? (IF FRAME IS NOT SQUARE, FIELD TRIMMING MAY BE REQUIRED. ASI IS NOT RESPONSIBLE FOR FIELD TRIMMING)
- 7.* VERTICAL DIMENSION? FROM TOP OF FRAME OPENING TO FINISHED FLOOR, NOT TO THE FRAME BOTTOM
- 8.* WHAT IS THE DOOR HANDING? (SELECT FROM HANDING DIAGRAM)
- 9.* LOCK/STRIKE TYPE, MAKE, SERIES, FUNCTION? (IF APPLICABLE)



DOOR FRAME OPENING DIMENSIONS		
DOOR OPENING WIDTH	A	3'-0"
DOOR OPENING HEIGHT	B	7'-0"

FEATURES

PANEL TYPE: ■ WHITE MOLDED FIBERGLASS	PANEL CAPPING: ■ NONE
WINDOW TYPE: ■ NONE	GLASS TYPE: ■ NONE
KICKPLATE - PULL SIDE: ■ NONE	KICK PLATE - PUSH SIDE: ■ NONE

STANDARD & LOOSE PARTS ITEMS

* PROVIDE

SPECIAL NOTES

TAG PANEL(S) AS: ***ADVISE***

*****ADVISE*****

- * PANEL TAG:
- * SWING: RH OR LH (SHOWN) OR RHR OR LHR (USE HANDING DIAGRAM)
- * EXISTING FRAME INFORMATION/DIMENSIONS:

APPROVAL DRAWING



5848 North 95th Court
Milwaukee, WI 53225
1-800-558-7068
www.asidoors.com

APPROVALS

FABRICATION CAN PROCEED ACCORDING TO THE SPECIFICATION SHOWN EXCEPT AS NOTED.

BY _____ DATE _____

ASI JOB NUMBER:
CUSTOMER ORDER NUMBER:
SOLD TO:
END USER:

QUANTITY OF DOORS:
DOOR MODEL NO: 220P
DOOR ASSEMBLY NO: SLSW-P
ELECTRICAL DRAWING NO:

TITLE
SINGLE SWING - PANEL ONLY

DRAWN BY KS	DATE	SHEET 1 OF	DRAWING NO.	REV.
----------------	------	---------------	-------------	------